



Company News

Interchem wins Contract for a 2.5 million tpa Cement Grinding Plant from CIMCO / Togo

Edited by on 5. Feb. 2020

Oelde, Germany -

Project Description

The order includes a truck unloading station 1000 tph, a storage facility for additives 25,000 tph, a truck loading station 1000 tph, 2 x 50,000 t clinker silos, 4 x Rotopacker, 8 x truck loading stations, 10 x truck scales and the corresponding laboratory equipment. The steel construction, the entire sheet metal fabrication, the subsystems, the electrical equipment, the complete engineering, the supervision of erection and commissioning are also included in the scope of supply and services. The entire equipment is supplied exclusively by renowned European manufacturers. All material conveyor belts are mounted in a closed gallery to ensure dust-free transport. This was planned because of the sensitive location in the immediate vicinity of the port in Lomé. The belt system is also designed for fully automatic ship unloading. Production is scheduled to start in Q1/2021.